This drawing is based on a design prepared by the MidWest requirements detailed in ACI 318-95. ground. The design is in accordance with ultimate strength design This drawing may be used for tanks which are above or below Publication TR-9, Circular Concrete Manure Tanks (March 1998). details concerning the design refer to MidWest Plan Service Plan Service (MWPS) at lowa State University. For more specific

Design Loading:

- 1. Manure load: 65 psf/ft. of depth
- 2. Soil backfill loads: 65 psf/ft. of depth with no surcharge or To meet this requirement see backfill details on this sheet. This requires the structure backfill to be adequately drained 60 psf/ft. of depth with 120 psf lateral surcharge.

Construction Notes:

- 1. Reinforcing steel for footing and walls shall have a tension yield point of fy = 60,000 psi. floor reinforcing steel grades. Refer to Sheet 2 for
- steel shall have a minimum inside radius of 3 bar diameters. For splice lengths refer to the table on Sheet 2. All bends in reinforcing
- 3. All concrete shall have a minimum 28 day compressive strength placement. of 4,000 psi. The mix design shall be submitted to NRCS prior to Unless shown otherwise in the construction specifications,
- the following requirements shall apply: Cement shall be Type I or Type II
- Slump 4 inches plus or minus 1 inch. Air content from 5 to 7 percent.
- Aggregate size maximum of 1 inch diameter.
- Cure concrete for a minimum of 7 days acceptable methods are: Construction joints – cleaned prior to subsequent concrete placement
- membrane forming curing compound at rate of 1 gal/150 s.f.
- leaving the forms in place
- -soaking / continuous spray
- 4. Construction joints may be used to ease construction. Refer to manufacturers recommendation for placing waterstop material. Engineer prior to placing the concrete. location of construction joints shall be approved by the
- Backfill shall be brought up uniformly around the tank. The maximum difference in the finished backfill elevations around the tank shall be 4 feet.
- 7. All construction methods shall meet OSHA regulations.
- Installation of this structure shall conform to NRCS Construction Specification 313.


90.


Safety Considerations:


- 2. Posts shall not be cast into the concrete wall, unless an 8" rebar is welded 1. The tank shall be surrounded by a chain link or woven wire fence.
- to the base of the post and the posts are capped at time of installation.
- 3. Safety stops shall be installed at pushoff locations to prevent accidental entry of equipment.
- 4. Warning signs shall be erected around the tank stating that entry may result in injury or death.

Vehicle Access

height from the edge of the tank, cast a 8 inch thick concrete slab along the traffic purpose of the slab is to distribute the loading along the tank wall and route by the tank. The concrete slab should be large enough to eliminate any prevent mud and erosion. wheel loads directly on the natural ground or backfill by the tank. The If heavy tank wagons, or trucks will be driven within a distance equal to the wall








ANK DIMENS


SNO

inches




WALL BACKFILL DETAIL-TYPICAL

- 1. Provide a minimum 4 inch diameter perimeter drain tile for wall backfill drainage. Outlet the tile at a location downslope where flow from the outlet may be monitored. Provide heavy wall pipe where backfill cover is < 24". Provide an animal guard on all outlets.
- 2. If a high water table is present a special drain design will be required under the tank floor to prevent uplift.
- To provide adequate drainage, the granular drain material shall be clean with maximum 5 percent fines. The maximum particle size shall be 1.5 inches.
 Provide a 12"x6" band of granular drain material under the footing every 50'
- on center around the tank perimeter.
- Provide minimum 3' of backfill over top of footing for frost protection.



** Vehicle access slab is required if heavy edge of the tank distance equal to the wall height from the tank wagons or trucks are driven within a

WALL BACKFILL DETAIL-VEHICLE ACCESS




U.S. DEPARTMEN

Typical wall joint detail PLAN VIEW

SHEET NO. 1 OF 2 PA-064

	٧			
•		·	Date	Date Approved
			2 <u>/99</u>	
ENT OF AGRICULTURE - NATURAL RESOURCES CONSERVATION SERVICE	Revised .	HLS 06	6 <u>/07</u>	Title



RIZG

FOUNDATION


Overhang

Construction Joint Approved Nonmetallic Waterstop (PVC)

Tie Bar Place Tie Bars @ Vertical Wall Steel

Wall Vertical Steel (A_{SV}) Wall Ring Steel (A_{Sr})

Place the 1st horizontal ring steel bar 1/2 the specified spacing above the footing.



60 ft.

#4 @ 12"#4 @ 12"#4 @ 8"

#4 @ 11"#4 @ 6" #4 @ 10

#4 @ 12"#4 @ 12 #4 @ 12"#4 @ 12'

#4 @ 10"#4 @ 12"#4 @ 9"

#4 @ 11

"#4 @ 7" #4 @ 11

4. See MidWest Plan Service, 3. Place vertical steel on the 2. Ring steel shall be located along the wall centerline.

Concrete Manure Tanks

Publication TR-9,

(March 1998) for alternative

outside of the ring steel.

#4 @ 12"#4 @ 12"

#4 @ 9"

#4 @ 11|" #4 @ 8" #4 @ 11

120 ft. 105 ft.

#4 @ 8"

#4 @ 12

′#4 @ 7"

#4 @ 8"

#5 @ 8"

#5 @ 9" #4 @ 8"

#5 @ 6" #5 @ 8" #5 @ 7" #5 @ 9"

#4 @ 8" |#4 @ 12" #4 @ 7"|

#4 @ 9"

#4 @ 6"

#4 @ 12"#4 @ 12"

"#4 @ 8" #4 @ 10"

#4 @ 6" #4 @ 8"

#5 @ 7" #5 @ 10

ring steel placement

(Tables 4, 5, 6, and 7).

#5 @ 8" #5 @ 12

#4 @ 6" |#4 @ 12| #4 @ 6" | #4 @ 8"

#5 @ 8" #5 @ 9"

#5 @ 6" #5 @ 7"

30 ft. 45 ft.

Bar Size

Spacing

Bar Size

Spacing Bar Size 8 ft. (8" thickness)

10 ft. (8" thickness)

12 ft. (10" thickness)

14 ft. (10" thickness)

WALL

STEEL REINFORCEMENT

Ring

Vertical Steel

Steel Asr

Vertical Steel Asv

Steel

Vertical Steel

Ring Steel

Vertical Steel Asv

For tank sizes not listed use the steel spacing & wall thickness from the next larger tank size

(Maximum height is 14 feet, maximum diameter 120 feet).

sr

ş




MONOLITHIC FOOTING/FLOOR PLACEMENT

Footing Width (B) Radial Steel (A_{S1})


3" Cover

Floor

WALL TO RING FOUNDATION DETAIL







			_			
	DETAIL OF THRO	Asr Asr Cut all vertical and ring steel one #5 bars are to be used a cone #5 bars are to be used a cone for spacing shall not be closs and not farther apart than Asr Ite diagonal bars to dowels when the diagonal bars to dowels when the cone was a cone with the cone and the cone was a cone when the cone and the co	:	#5	#4	וויס
	_ OF PIPE PROTRUDING THROUGH A WALL	Opening Ope			76 inches	(
SHEET NO. 2 OF	CAD FILE NAME PATr9sht2.dwg DRAWING NO. PA-064	PENNSYLVANIA ROUND TANK Details	<u> </u>			
F 2	٥	U.S. DEPARTMENT OF AGRICULTURE - NATURAL RESOURCES CON	SERVATI	ION S	ERVI	CE

	* See PA-004	This table is for floors on coarse granular or cohesive material. For floors on sand or pervious geotextile, A _s may be reduced 50%.	>140' ≤ 200'	>90' ≤ 140'	>60' ≤ 90'	>30' ≤ 60'	≤ 30'	JOINTS *	DISTANCE	$\neg \neg$		
	and t	for fice, As	.19	.12	.087	.058	.029	A_S	FOR	L00		
	PA-004 and PA-063 for Joint details	oors on or floors may be	#4 @	#4 @	#3 @	6x6-1	6X6-N	£Χ	5,	FLOOR STEEL		
<u>></u> _	for Join	coarse on san	12"	18"	15"	6x6-W2.9xW2.9	6X6-W1.4xW1.4	EXAMPLE	THICK FLOOR			
U > U	t details	granular or d or pervic 1 50%.				9 (6 ga.)	4 (10 ga.)		OR	·		
		suc		•	•							
Designe	ed			Da		ppro	ved _					Date
Drawn					Title							
CADD _ WAC												
Revised HLS				12/9	99 1	itle _		_				